	App Qty	Description of work	Approved Rates of m/s KRIDL		
			Unit	Rate in Figures	Rate in Words
37	1.00	Supplying and fixing surface/flush mounting unbreakable PVC modular box suitable for mounting modular switch plates with due groove cutting in Brick/C.C wall, including necessary rawl plugs, Machine/NF screws etc., complete.10-12Way. item no 3.4.4 page no 15	rmt	152.00	Rupees One Hundred Fifty Two Only
38	10.00	Supplying and fixing of modular switch/ Socket/stepped electronic fan regulator/ dimmer/telephone socket etc on existing modular switch plate as per IS 3854 and IS 1293 GROUP A 6Amps one way. item no 3.7A.1 page no 16	no	63.00	Rupees Sixty Three Only
39	30.00	Laying of UG Cables by trenchless technology by adopting horizontal boring & Drawing of cable including preparation at site With HDPE Pipe iii) Normal soil 6" bore size item no 48.3 page no	rmt	1031.00	Rupees One Thousand Thirty One Only
40	10.00	GI Pipes B - ClassGI Pipe - 150 mm Dia Dia 768058 directions of the Engineer-In-charge of the work	rmt	1144.00	Rupees One Thousand One Hundred Forty Four Only
41	291.25	Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per specification with all lead and lift and directions of the Engineer-In-charge of the work . Item no 2.4 page no 5 SR	cum	369.82	Rupees Three Hundred Sixty Nine And Paise Eighty Two Only
42	31.50	Providing and Spreading of Sand with all lead and lift and directions of the Engineer-In-charge of the	cum	2762.58	Rupees Two Thousand Seven Hundred Sixty Two And Paise Fifty Eight Only
43	63.00	Providing and filling in foundation with granite / trap broken metal 100mm and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift complete as per specification. with all lead and lift and directions of the Engineer-In-charge of the work	cum	2790.02	Rupees Two Thousand Seven Hundred Ninety And Paise Two Only

Executive Engineer
Project Division
Yelahanka Zone

Contrator

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

	App Qty	Description of work	Approved Rates of m/s KRIDL		
			Unit	Rate in Figures	Rate in Words
44	204.47	Providing and laying in position Plain Cement Concrete of mix 1:3:6 with OPC cement @ 220kgs ,with 40mm and down size graded granite metal coarse aggregates @ 0 .892 cum and fine aggregates @ 0.465cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, in foundation including cost of all materials,labour, HOM of machinery ,curing complete as per specifications.	cum	6594.11	Rupees Six Thousand Five Hundred Ninety Four And Paise Eleven Only
45	252.03	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready mixedf concrete for RCC works laid in 15 cms thick layers and well compated including vibrating, curing,etc., with all lead and lifts etc complete(excluisive of cost of steel and fabrication charges) Ready Mixed Cement Concrete for Beams, Staircase and Roof with M-25(for Side Walls and Bottom)	cum	8320.40	Rupees Eight Thousand Three Hundred Twenty And Paise Forty Only
46	63.60	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as Walls at any thickness, incluidng attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specfiications.	sqm	382.89	Rupees Three Hundred Eighty Two And Paise Eighty Nine Only
47	1788.90	Providing Ceramic tiles of approved make shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing, complete as per specifications.of size 30 x 30 cms 6mm thick	sqm	1536.80	Rupees One Thousand Five Hundred Thirty Six And Paise Eighty Only
48	1176.23	Providing pre cast urocon tiles, red colour for footpath 20mm thickusing marble chilps at 7-10 nominalsize laid on bed CM 1:3 mix & jointd with red oxide cement slurry mixed pigment to match the shade of tiles, rubbing polishing , oxalicacid was, wax polish including cost of all materials and labour (Approved Rates)	sqm	1300.00	Rupees One Thousand Three Hundred Only

Contrator

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Project Division
Yelahanka

	App Qty	Description of work	Approved Rates of m/s KRIDL		
			Unit	Rate in Figures	Rate in Words
49	275.85	Providing and constructing precast concrete Solid Blocks with compressive strength not less than 35 kg/sqm with cement mortar 1:4 masonry (quion, jamb, closer blocks) with Solid Concrete Blocks of size 40x20x20cms confirming to I.S 2185/1965 in Superstructure including cost of all materials, labour charges, scaffolding, curing complete as per specifications.	sqm	1185.27	Rupees One Thousand One Hundred Eighty Five And Paise Twenty Seven Only
50	135.00	Providing TMT Steel Reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.TMT Bars Fe 500with all lead and lift and directions of the Engineer-In-charge of the work	qtl	7903.53	Rupees Seven Thousand Nine Hundred Three And Paise Fifty Three Only
51	553.05	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherver required smooth rendering, : Providing and removing scaffolding, cost of materials, labour, curing complete as per specifications and direction of the Engineer in charge Providing lime rendering for plastering to wall and ceiling including cost of mate3rials labour curing complete as per specifications Internal wall platering with all lead and lift and directions of the Engineer-In-charge of the work	sqm	335.85	Rupees Three Hundred Thirty Five And Paise Eighty Five Only
52	501.00	Providing ACE paint to external walls of approved colour and shade over prime's coat.after brooming & cleaning the surface and applying two coats of ACE paint with cost of all material,labour,lead lift with loading unloading etc.complete as per direction of Engineer in charge of work.(Approved rates)	sqm	180.00	Rupees One Hundred Eighty Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Project Division
Yelahanka Zone

	App Qty	Description of work	Approved Rates of m/s KRIDL		
			Unit	Rate in Figures	Rate in Words
53	225.00	Providing and fixing to wall, ceiling and floor, low density polyethylene pipes 6.00 kgf/s.cm working pressure 160mm outside diameter, compression type fittings, wall clips, making good the wall, ceiling and floor including cost of all materials, labour charges, HOM of equipments and testing, excluding cost of fittings, complete as per specifications. (2 runs)	rmt	538.40	Rupees Five Hundred Thirty Eight And Paise Forty Only
54	9.00	Providing and constructing granite / trap / basalt Size Stone Masonry in cement mortar 1:6, stone hammered dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of maerials, labour, curing with all lead and lifts, hire charges of machinaries, loading, unloading, levelling as per specification and direction of the Engineer-in-charge	cum	5275.55	Rupees Five Thousand Two Hundred Seventy Five And Paise Fifty Five Only
55	32.40	Providing and fixing pull and push type rolling shutter of approved ake out of 19 guage,75mm wide cold rolled steel laths of conves corrgation, with side guides and bottom rail, with interlaocking arrangements for steel laths by means of alternate clips suspension shaft whith high tension coil type spring two number ,mounted on specially desigend pipe shaft,with bracket two plastes ,guide channels, ball bearning arrangement for inside & out side locking with pus & pull operation complete including pulling hooks,4 nos .Handles with all fitting and accessores, painted with a coat of red paint (withouttop cover) cost of materials,labour,HOM of machinery complete as per specification	sqm	3740.06	Rupees Three Thousand Seven Hundred Forty And Paise Six Only

H.V. 5/3/18

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Enginee
Project Divisio
Yelahanka Zon

	App Qty	Description of work	Approved Rates of m/s KRIDL		
			Unit	Rate in Figures	Rate in Words
56	1000.00	Fabricating, supplying & erecting M.S. angular Truss of all spans as per approved designs and drawing. The entire truss is anchored suitably by using 4 nos of of M.S. anchor bolts at each support, with base plate and shoe plate.The work includes cutting, straightening, placing in position of M.S angle and wleding wherever necessary, and applying one coat of red oxide primer coat to all the members including cost of all materials, labour charges, & hire charges of machineries for cutting, welding, grinding & erection equipments, etc., complete as per specification	kgs	152.90	Rupees One Hundred Fifty Two And Paise Ninety Only
57	24.20	Providing and installing of pre painted Galvolume iron Trapezoidal profiled sheet of approved make 1060 mm width (1000 mm cover width), 28-30 mm crest height with crest distance of 200 mm c/c with 2 ribs at the centre for stiffening. The total coated thickness (TCT) of the sheet will be 0.47 mm +/- 0.02 mm tolerance Zinc-Alu Alloy coating AZ150 gsm as per ASTM 1397/A755-550 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 20-22 microns using self drilling/self tapping screws of 25 mm length, to be fixed over the existing purlins, rafters, channels and trusses.	sqm	1006.24	Rupees One Thousand Six And Paise Twenty Four Only
58	3.00	Supply, installtion, testing and commissioning of RECIRCULATING PUMPS 10 HP monoblock centrifugal pump 400V 3ph discharge:45 LPS at 13m head suction size:150mm, delivery: 150mm includes 1no standby directions of the Engineer-In-charge of the work	nos	74290.00	Rupees Seventy Four Thousand Two Hundred Ninety Only
59	72.00	Supply, installtion, testing and commissioning of FLOOR INLETS bottom inlet for concrete with S.S. screws made of ABS plastic. Max. flow: 10cum/hr 2 inches threaded fitting directions of the Engineer-In-charge of the work	nos	875.00	Rupees Eight Hundred Seventy Five Only
60	3.00	Supply, installtion, testing and commissioning of MAIN DRAIN GRATING COVER, material : SS 304 500mm x 500mmx6mm thick with slot openings of 6mm directions of the Engineer-In-charge of the work	nos	21000.00	Rupees Twenty One Thousand Only

Executive Engineer
Project Division
Yelahanka Zone

Contrator

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

	App Qty	Description of work	Approved Rates of m/s KRIDL		
			Unit	Rate in Figures	Rate in Words
61	72.00	Supply, installtion, testing and commissioning of SUCTION INLETS ABS plastic, 2 inches external DIA glue type Flow:3.5 cum/hr, with threaded cap directions of the Engineer-In-charge of the work	nos	875.00	Rupees Eight Hundred Seventy Five Only
62	1.00	Supply, installtion, testing and commissioning of MAINTENANCE KIT COMPRISING OF: a) LEAFE RAKE Deep bag net made in polypropylene and polyester netting butterfly nut connection directions of the Engineer-In-charge of the work	nos	2000.00	Rupees Two Thousand Only
63	1.00	Curved brushes made in polypropylene for pool basins and scum liners directions of the Engineer-In-charge of the work	nos	2400.00	Rupees Two Thousand Four Hundred Only
64	1.00	Straight brushes made in polypropylene for pool basins and scum liners directions of the Engineer-In-charge of the work	nos	2400.00	Rupees Two Thousand Four Hundred Only
65	1.00	Reinforced aluminium telescopic handle 2.4/4.8m with clip connection directions of the Engineer-In-charge of the work	nos	4400.00	Rupees Four Thousand Four Hundred Only
66	1.00	Metallic Anodized Aluminium Vacuum head directions of the Engineer-In-charge of the work	nos	19700.00	Rupees Nineteen Thousand Seven Hundred Only
67	1.00	Extensible handles for cleaning attachments in anodized aluminium which can be adapted to the entire range of cleaning equipment, brushes, leaf skimmers and scoops 10m long directions of the Engineer-In-charge of the work	nos	4375.00	Rupees Four Thousand Three Hundred Seventy Five Only
68	1.00	Transparent blue plastic vacuum hose 11/2" dia 30mtr slong including hose cuffs for connection to suction inlets directions of the Engineer-In-charge of the work	nos	7100.00	Rupees Seven Thousand One Hundred Only
69	1.00	Supply, installtion, testing and commissioning of POOL CLEANER trolly mounted with 5 Hp self priming pump with prefillter, starter and 63mm flexible hose directions of the Engineer-In-charge of the work	nos	100000.00	Rupees One Lakh(s) Only
70	20.00	Supply, installtion, testing and commissioning of ANCHOR HOOKS STAINLESS STEEL fixed to end walls for lane ropes directions of the Engineer-In-charge of the work	nos	3300.00	Rupees Three Thousand Three Hundred Only

Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Project Division
Yelahanka Zone

	App Qty	Description of work	Approved Rates of m/s KRIDL		
			Unit	Rate in Figures	Rate in Words
71	1.00	Supply, installtion, testing and commissioning of GAS CHLORINATION SYSTEM vacuum type cylinder mounted gas (DCM) chlorinator capacity 0-500 gms/hr, chlorination system consisting of filter Assembly, Vacuum Regulator, flow meter assembly, control valve assembly, injector assembly including booster pump assembly and piping complete directions of the Engineer-In-charge of the work	nos	327750.00	Rupees Three Lakh(s) Twenty Seven Thousand Seven Hundred Fifty Only
72	2.00	Supply, installtion, testing and commissioning of BUTTERFLY VALVES Wafer type PN 10 STD,replacable EPDM sleeve CI body with SS316 disc a) 10 INCHES directions of the Engineer-In-charge of the work	nos	26220.00	Rupees Twenty Six Thousand Two Hundred Twenty Only
73	3.00	Supply, installtion, testing and commissioning of NON RETURN VALVES Material: gun metal Size: 8 inches directions of the Engineer-In-charge of the work	nos	19700.00	Rupees Nineteen Thousand Seven Hundred Only
74	90.40	Supply, installtion, testing and commissioning of UPVC PIPES a) 400 MM DIA 6 KG/SQCM directions of the Engineer-In-charge of the work	rmt	4700.00	Rupees Four Thousand Seven Hundred Only
75	29.00	d) 63 MM DIA 10KG/SQCM directions of the Engineer-In-charge of the work	rmt	260.00	Rupees Two Hundred Sixty Only
76	131.15	e) 160 MM DIA 6 KG/SQCM directions of the Engineer-In-charge of the work	rmt	13100.00	Rupees Thirteen Thousand One Hundred Only
77	9.00	Supply, installtion, testing and commissioning of UPVC ELBOW 6 KG/SQCM	nos	26800.00	Rupees Twenty Six Thousand Eight Hundred Only
78	5.00	d) 63 MM directions of the Engineer-In-charge of the work	nos	175.00	Rupees One Hundred Seventy Five Only
79	1.00	Supply, installtion, testing and commissioning of STARTING BLOCKS FIBREGLASS 400 mm height non slip finish 0.5x 0.5m with nos 1 to 9 with anchoring fixtures directions of the Engineer-In-charge of the work	nos	26220.00	Rupees Twenty Six Thousand Two Hundred Twenty Only
80	1000.00	Providing supplying chlorin granules	kgs	600.00	Rupees Six Hundred Only
81	15000.00	Providing supplying filter media using quarzite stones crushed into 0 to 4mm and filling the same into exisisting filters	kgs	27.00	Rupees Twenty Seven Only
82	2000000.00	Supply filling portable water to main pool and baby pool	liters	0.10	Rupees And Paise Ten Only

Contrator

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Project Division
Yelahanka Zone

5/3/18

	App Qty	Description of work	Approved Rates of m/s KRIDL		
			Unit	Rate in Figures	Rate in Words
83	228.89	Providing and laying Flooring using pre polished water cut/gang saw 19mm thick grey granite laid over bed of 20mm thick 1:4 cm and jointed with neat cement slutty mixed with pigment to match shade of granite slabs including laying POP on finished surfaqce and cleaning the surface including the cost of all m,aterials and laboutsd etc. complete as per specifications. with all lead and lift and directions of the Engineer-In-charge of the wor	sqm	2595.30	Rupees Two Thousand Five Hundred Ninety Five And Paise Thirty Only
84	4.00	Supply, installtion, testing and commissioning of STAINLESS STEEL LADDERS made of SS 316 with pipe dia 38mm with non skid steps with embossed finish or checkered finish overflow model No of steps = 3 directions of the Engineer-In-charge of the work	nos	51750.00	Rupees Fifty One Thousand Seven Hundred Fifty Only
85	2.00	No of steps = 4 directions of the Engineer-In-charge of the work	nos	55315.00	Rupees Fifty Five Thousand Three Hundred Fifteen Only
86	12.60	Providing and fixing factory made splendor of solid core single leaf rigid composite polymer laminated seal wood ,door.shutter of required thickness,manufactured out of solid core door confirming to IS 2202(part-1)1991,laminated with 0.8mm thick polymer termite water resistant and fire retrardant with superior gluring based on vaccum lamination technology and with various pre moulded design on both faces confirming to IS 6307-1985,USING Adeshive confirming to IS 4835-1979 and door shutters tested in confirming to IS 4020-1994 The finish of shutters will be TEAK/CEDAR/ROSE/,WOOD/WALNUT plain colours. WHITE /IVORY/BEIGE /LIGHTGREY.Excluiding cost of fixtures and inclusive of suppley of shutters to respective work spot 9.93 with door shutter 35mm thick	sqm	4769.82	Rupees Four Thousand Seven Hundred Sixty Nine And Paise Eighty Two Only

5/3/18

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Project Division
Yelahanka Zone